10 1/2"

8 1/8"

3/4" Plywood Hanger plate. Size to width of stair and attach to all stringers.

7"

Stringer Detail- 2x12 Fir

Facing- 1/4" Masonite

10 1/2"

7"

10 1/2"

Half Newel Post Attach to wall

Plowed Poplar Handrail

7"

5 7/8"

39" Oak Baluster Menards K5141-39 Cut to fit

3-1"

3/4" Trim

Facing covers edge of risers and aligns with bottom of treads

Scenery wall

2'-5"

5 1/4"

5 1/4"

5 1/4"

8'-0"

2'-0 5/8"

4'-0 3/8"

3/4" x 7" Particle Board risers

9"

1'-4"

11 1/4" x 1 1/8" Particle Board Tread (stock item at Menards). Treads should overhang downstage stringer by 1/4".

Edge of tread should be flush with masonite facing. Attach Oak BullnoseCap to edge of tread after facing is applied.

Align with front edge of riser

3 1/2"

7"

Platforms

1'-0"

Stage Floor

Bullnose Cap

Producing Organization	Production Title	Director	Drawing Information		Scale		Drawing Number
St. Olaf Theater	*August: Osage County*	M. Gibbs	Date 2/18/17 Revision: 2/18/17 Drawn By B. Bjorklund		3/4 "=1'-0"	Elevations	X of X